

H17年度 汚染拡散防止対策工事平面図 (H17/7)

- ① 仮設浄化P (400m<sup>3</sup>/day)  
H16/3-H17/7
- ⑩ 雨水排水路工事  
H16/9-H17/5
- ⑥ 浸出水導水路(管理設)  
H16/9-H17/5
- ⑪ 防災調整池 (V=11,960m<sup>3</sup>)  
H16/3-H17/5
- ⑧ 浸出水処理施設  
(150m<sup>3</sup>/day) H16/3-H17/5  
運転開始 H17/6-
- ⑦ 浸出水貯留池 (V=12,300m<sup>3</sup>)  
H16/3-H17/5  
貯留開始 H17/6-
- ⑫ 場内整備工事H17/4-8 H17
- ⑭ 工事用道路整備(町道)  
L=558m, W=5.0m

- 廃棄物掘削 (Aエリア) H16/12-
- ② 表面遮水工 6,880m<sup>2</sup>  
H15/12-H16/5
- 廃棄物処理・選別ヤード H17/1-
- ⑬ 洗車設備 H16/7完、運転中

- ④ 鉛直遮水壁工 L= 981m H17-19
- ③ (暫定)表面遮水工 56,000m<sup>2</sup> H17

- ⑮ 場内道路整備工事
- ⑤ 浸出水貯留槽、雨水接合槽

- ⑭ 工事用道路整備(町道)  
L=641m, W=5.0m

凡例

- 今年度実施工事
- 過年度より実施中
- 工事終了済

県道 道前・浄法寺線



汚染拡散防止対策工事 概略工程表

	工 事 内 容	概 要	工事金額 (百万円)	H15年度												H16年度												H17年度												H18年度												H19年度											
				#			#			#			#			#			#			#			#			#			#			#			#																										
				1	2	3	4	5	6	7	8	9	10	11	12	1	2	3	4	5	6	7	8	9	10	11	12	1	2	3	4	5	6	7	8	9	10	11	12	1	2	3																					
緊急の対策工事	H15 電力工事負担金	高圧電線路新設工事 2,600m 電柱建設工事 57本	6.1																																																												
	H15 表面遮水工事	表面遮水工 6,880m <sup>2</sup> 雨水排水工 563m、浸出水排水工 334m	51.8							H15/12												H16/5																																									
	H15 工事用道路整備工事(田子町道)	県道～投棄現場間 640 m 県道～ラグーン部エリア 558 m	66.1																																																												
	H15～H17 仮設浄化プラント工事	仮設浄化プラント設置・運転・維持管理・撤去 1式 (処理能力 400m <sup>3</sup> /日、処理項目 pH、濁度)	122.5							H16/1																																																					
長期的対策工事	H16 浸出水導水路及び雨水排水路工事	浸出水導水管 432.7 m 雨水排水路 357.5 m	97.5																			H16/9												H17/5																													
	H15～H17 浸出水処理施設工事	建屋建設(地下1,地上2,延1390m <sup>2</sup> )、機械・配管・電気計装工 (処理能力 150m <sup>3</sup> /日 処理項目 pH, BOD, COD, SS, T-N, T-P, その他有害物質, DXN類)	1,995.0							H16/3												H17/5						(運転・維持管理)																																			
	H15～H17 浸出水貯留池及び防災調整池工事	浸出水貯留池1式 (V=12,300 m <sup>3</sup> ) 防災調整池1式 (V=11,960 m <sup>3</sup> )	491.6							H16/3												H17/5																																									
	H16 場内整備工事(ラグーン部整備)	法面工 1式 側溝工 1式 進入道路工 1式	49.6																															H17/4						H17/8																							
	H17 (一次)表面遮水工事 (3工区に分割)	一次表面遮水工 56,000 m <sup>2</sup> 場内道路工 907 m 雨水排水工 1,288 m	122.8																															H17/5						H17/8																							
	H17～H19 鉛直遮水壁工事 (5工区に分割)	遮水壁工 981.9 m 表面遮水工 30,330 m <sup>2</sup> 浸出水貯留槽 1槽	1,698.3																															H17/6																		H19/7											
廃棄物掘削・処理工事	H15 洗車設備工事	洗車設備工、洗車設備上屋工 8.5×32.0m 洗車場取付け道路 166m	85.3							H16/4																																																					
	H15 廃棄物掘削工事	廃棄物掘削工 6,550 m <sup>3</sup> 洗車設備維持管理 1式 仮設道路工 1式	41.8													H16/12																																															
	H15 廃棄物処理委託工事	選別ヤード造成工 1式 廃棄物選別積込工	136.2																			H17/1/12～3/31																																									
	H16 廃棄物掘削工事 廃棄物処理委託工事 洗車設備維持管理	廃棄物掘削・選別・積込工 18,100 m <sup>3</sup> 洗車設備維持管理 1式	158.7																			H17/4/1-																																									
	H17以降	廃棄物掘削工事 廃棄物処理委託工事 洗車設備維持管理																																																								H24まで					
計			5,123.3																																																												